

Chumnubri Rural Municipality
Office of Rural Municipal Executive

Sirdibas ,Gorkha
BILL OF QUANTITY

Project Name : Philim Larke Pass Padmarga Staronnati

F.Y.2083/084

Project Location : Chumnubri Rural Municipality Ward No -03,04 & 05 of different location, Sirdibas Gorkha

Contract ID: CNRM/WORKS/NCB/01/2083/84

S. No.	Description of Items	Quantity	Unit	Rate (NRs)		Amount (NRs)
				In Figure	In Words	
A	General Item					
1.0	Providing and installation of project information boards with size of 0.75X0.60 m with Ms squire post of 2"X 2" of minimum height of 7 ' as per specification and instruction of site engineer:	3.00	PS	10000.00	Ten thousand	30000.00
2.0	Insurance of the loss of damage to works, plant, material, equipment property and personel injury of death including third party insurance as per contract document (SS/SP 117)@ 1% of total cost.	1.00	PS	50000.00	Fifty thousand	50000.00
3.0	Provide and establish the labor camps and adequate drinking water facility and toilets for labors and demolish camp site , safety equipment and re-instate the ground as per specifications and as instructed by site Engineer	1.00	PS	50000.00	Fifty thousand	50000.00
	Provision of additional site lab and laboratory equipment for construction material test like cement, sand,aggregate,filling materials,concrete cubes etc. and field test including all	1.00	PS	50000.00	Fifty thousand	50000.00

Chumnubri Rural Municipality
Office of Rural Municipal Executive

Sirdibas ,Gorkha
BILL OF QUANTITY

Project Name : Philim Larke Pass Padmarga Staronnati

F.Y.2083/084

Project Location : Chumnubri Rular Municipality Ward No -03,04 & 05 of different location, Sirdibas Gorkha

Contract ID: CNRM/WORKS/NCB/01/2083/84

S. No.	Description of Items	Quantity	Unit	Rate (NRs)		Amount (NRs)
				In Figure	In Words	
B	Civil Item					
1.0	Excavation in Roadway, Drain and foundation in Soil including removal and satisfactory disposal of the materials upto a lead of 50m. (In ward no.3 at diffrent location as per instruction of engineer)	42.30	Cu.m			
2.0	Excavation in Roadway, Drain and foundation in Soil including removal and satisfactory disposal of the materials upto a lead of 50m. (In ward no.5 at diffrent location as per instruction of engineer)	34.58	Cu.m			
3.0	Excavation in Roadway, Drain and foundation in Soil including removal and satisfactory disposal of the materials upto a lead of 50m. (In ward no.4 at diffrent location as per instruction of engineer)	87.45	Cu.m			
4.0	Providing and laying Manual mixed of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M 15. It includes mixing,placing in position, vibrating, compacting,finishing,curing and all other incidents,including necessary formwork.. all complete as per drawings, specifications and the instructions of the Engineer. (In ward no.3at diffrent location as per instruction of engineer)	57.60	Cu.m			

Chumnubri Rural Municipality
Office of Rural Municipal Executive

Sirdibas ,Gorkha
BILL OF QUANTITY

Project Name : Philim Larke Pass Padmarga Staronnati

F.Y.2083/084

Project Location : Chumnubri Rular Municipality Ward No -03,04 & 05 of different location, Sirdibas Gorkha

Contract ID: CNRM/WORKS/NCB/01/2083/84

S. No.	Description of Items	Quantity	Unit	Rate (NRs)		Amount (NRs)
				In Figure	In Words	
5.0	Providing and laying Manual mixed of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M 15. It includes mixing,placing in position, vibrating, compacting,finishing,curing and all other incidents,including necessary formwork.. all complete as per drawings, specifications and the instructions of the Engineer.all complete as per drawings, specifications and the instructions of the Engineer. (In ward no.5 at diffrent location as per instruction of engineer)	51.68	Cu.m			
6.0	Providing and laying Manual mixed of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M 15. It includes mixing,placing in position, vibrating, compacting,finishing,curing and all other incidents,including necessary formwork.. all complete as per drawings, specifications and the instructions of the Engineer.all complete as per drawings, specifications and the instructions of the Engineer. (In ward no.4 at diffrent location as per instruction of engineer)	133.65	Cu.m			

Chumnubri Rural Municipality
Office of Rural Municipal Executive
Sirdibas ,Gorkha
BILL OF QUANTITY

Project Name : Philim Larke Pass Padmarga Staronnati

F.Y.2083/084

Project Location : Chumnubri Rular Municipality Ward No -03,04 & 05 of different location, Sirdibas Gorkha

Contract ID: CNRM/WORKS/NCB/01/2083/84

S. No.	Description of Items	Quantity	Unit	Rate (NRs)		Amount (NRs)
				In Figure	In Words	
7.0	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications and instruction of the Engineer. The complete item including all lead & lift. (In ward no.3 at diffrent location as per instruction of engineer)	97.65	Cu.m			
8.0	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications and instruction of the Engineer. The complete item including all lead & lift. (In ward no.5 at diffrent location as per instruction of engineer)	43.88	Cu.m			
9.0	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications and instruction of the Engineer. The complete item including all lead & lift. (In ward no.4 at diffrent location as per instruction of engineer)	199.35	Cu.m			

Chumnubri Rural Municipality
Office of Rural Municipal Executive

Sirdibas ,Gorkha
BILL OF QUANTITY

Project Name : Philim Larke Pass Padmarga Staronnati

F.Y.2083/084

Project Location : Chumnubri Rular Municipality Ward No -03,04 & 05 of different location, Sirdibas Gorkha

Contract ID: CNRM/WORKS/NCB/01/2083/84

S. No.	Description of Items	Quantity	Unit	Rate (NRs)		Amount (NRs)
				In Figure	In Words	
10.0	Supply & delivery of Chainlink mesh wire 10 gauge of 3"*3" for Fencing all complete as per drawings, specifications and instruction of the Engineer. The complete item including all transportation & fitting charge. (In ward no.3 at diffrent location as per instruction of engineer)	111.60	Sq.m			
11.0	Supply & delivery of Chainlink mesh wire 10 gauge of 3"*3" for Fencing all complete as per drawings, specifications and instruction of the Engineer. The complete item including all transportation & fitting charge. (In ward no.4 at diffrent location as per instruction of engineer)	135.00	Sq.m			
12.0	Supply & delivery of 50 mm dia GI Pipe MC circular of 1.2 m long vetical post for railing with 'Fabrication complete item including all transportation & fitting charge. (In ward no.3 at diffrent location as per instruction of engineer)	79.20	R.m			

Chumnubri Rural Municipality
Office of Rural Municipal Executive

Sirdibas ,Gorkha
BILL OF QUANTITY

Project Name : Philim Larke Pass Padmarga Staronnati

F.Y.2083/084

Project Location : Chumnubri Rular Municipality Ward No -03,04 & 05 of different location, Sirdibas Gorkha

Contract ID: CNRM/WORKS/NCB/01/2083/84

S. No.	Description of Items	Quantity	Unit	Rate (NRs)		Amount (NRs)
				In Figure	In Words	
13.0	Supply & delivery of 50 mm dia GI Pipe MC circular of 1.2 m long vetical post for railing with 'Fabrication complete item including all transportation & fitting charge. (In ward no.4 at diffrent location as per instruction of engineer)	120.00	R.m			
14.0	Providing and laying of dry Stone Masonry Work as per Drawing and Technical Specifications. (In ward no.3 at diffrent location as per instruction of engineer)	51.23	Cu.m			
15.0	Providing and laying of dry Stone Masonry Work as per Drawing and Technical Specifications.. (In ward no.5 at diffrent location as per instruction of engineer)	16.88	Cu.m			
16.0	Providing and laying of dry Stone Masonry Work as per Drawing and Technical Specifications.. (In ward no.4 at diffrent location as per instruction of engineer)	49.73	Cu.m			

Chumnuhari Rural Municipality
Office of Rural Municipal Executive

Sirdibas ,Gorkha
BILL OF QUANTITY

Project Name : Philim Larke Pass Padmarga Staronnati

F.Y.2083/084

Project Location : Chumnuhari Rural Municipality Ward No -03,04 & 05 of different location, Sirdibas Gorkha

Contract ID: CNRM/WORKS/NCB/01/2083/84

S. No.	Description of Items	Quantity	Unit	Rate (NRs)		Amount (NRs)
				In Figure	In Words	
17.0	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications. and making weep holes if necessary. (In ward no.3 at different location as per instruction of engineer)	2.25	Cu.m			
18.0	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications. and making weep holes if necessary. (In ward no.5 at different location as per instruction of engineer)	2.25	Cu.m			
19.0	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications. and making weep holes if necessary. (In ward no.4 at different location as per instruction of engineer)	2.70	Cu.m			
20.0	Cutting, bending, placing in position as shown in the drawing & binding by GI wire of reinforcement steel bar for RCC works including haulage distance upto 30m. (In ward no.3 at different location as per instruction of engineer)	55.31	K.g			

Chumnubri Rural Municipality
Office of Rural Municipal Executive

Sirdibas ,Gorkha
BILL OF QUANTITY

Project Name : Philim Larke Pass Padmarga Staronnati

F.Y.2083/084

Project Location : Chumnubri Rular Municipality Ward No -03,04 & 05 of different location, Sirdibas Gorkha

Contract ID: CNRM/WORKS/NCB/01/2083/84

S. No.	Description of Items	Quantity	Unit	Rate (NRs)		Amount (NRs)
				In Figure	In Words	
21.0	Cutting, bending, placing in position as shown in the drawing & binding by GI wire of reinforcement steel bar for RCC works including haulage distance upto 30m.(In ward no.4 at diffrent location as per instruction of engineer)	134.32	K.g			
Total of B (In Figure)						
Total of B (In Word)						
13 % VAT of B						
Total with VAT(B)						
PS Item				180000.00		
Total with VAT & PS						

Signature of Authorised Person:

Name of Authorised Person:

Contractor's Name:

Address and Telephone No.:

Seal:

Date: