

Chumnubri Rural Municipality
Office of Rural Municipal Executive
Sirdibas ,Gorkha
BILL OF QUANTITY

Project Name : SamaGaun PCC Bato Nirman Yojana

F.Y.2083/084

Project Location : Chumnubri Rural Municipality Ward No -01, SamaGaun , Gorkha

Contract ID: CNRM/WORKS/NCB/05/2083/84

S. No.	Description of Items	Quantity	Unit	Rate (NRs)		Amount (NRs)
				In Figure	In Words	
A	General Item					
1.0	Providing and installation of project information boards with size of 0.75X0.60 m with Ms square post of 2"X 2" of minimum height of 7 ' as per specification and instruction of site engineer:	1.00	PS	10000.00	Ten thousand	10000.00

Chumnubri Rural Municipality
Office of Rural Municipal Executive
Sirdibas ,Gorkha
BILL OF QUANTITY

Project Name : SamaGaun PCC Bato Nirman Yojana

F.Y.2083/084

Project Location : Chumnubri Rular Municipality Ward No -01, SamaGaun , Gorkha

Contract ID: CNRM/WORKS/NCB/05/2083/84

S. No.	Description of Items	Quantity	Unit	Rate (NRs)		Amount (NRs)
				In Figure	In Words	
B	Civil Item					
1.0	Excavation in Roadway, Drain and foundation in Soil including removal and satisfactory disposal of the materials upto a lead of 50m as per instruction of engineer.	20.88	Cu.m			
2.0	Providing and laying Manual mixed of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M 15. It includes mixing,placing in position, vibrating, compacting,finishing,curing and all other incidents,including necessary formwork.. all complete as per drawings, specifications and the instructions of the Engineer	31.32	Cu.m			
3.0	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications and instruction of the Engineer. The complete item including all lead & lift.	62.64	Cu.m			
Total of B (In Figure)						
Total of B (In Word)						
13 % VAT of B						
Total with VAT(B)						
PS Item				10000.00		
Total with VAT & PS						